

# ENGINEERING DEPARTMENT BID SCHEDULE MAJOR PUBLIC WORKS IMPROVEMENT PROJECTS

**2nd Quarter – April to June 2020 - Updated 04/29/2020**

<b>2020</b>			
<b>Projected Bid</b>		<b>Project</b>	<b>Project Description</b>
Bid Closed	SS	<p>Stonewall Alley Paving Reconstruction</p> <p>Bid closed March 19, 2020. Will be awarded at Council May 5</p>	<p>Reconstruction of the alley serving Lots 1 thru 7 of the Country Club Additions (1110 to 1134 Stonewall St.) approx. 500 LF. Majority of the alley will be constructed as a structural slab supported on 18" dia. drilled piers spaced at 10-ft o.c.</p> <p>Estimated Construction Cost: \$380,000</p>
Bid Closed	SS	<p>Pedestrian Path/SW from Forest/Jupiter DART Station to Marie Curie Blvd</p> <p>Bid closed April 16, 2020. Will be awarded at Council May 19.</p>	<p>Construction of sidewalk, pedestrian curb ramps, striping, bollards, and drainage improvements along a 1.7 mile route beginning at Forest/Jupiter DART Station and ending at the existing medical facility located at Clara Barton Blvd &amp; Marie Curie Blvd. The sidewalk runs along Barnes Dr, Edgewood Dr, Montgomery Park, N. International Rd, Walnut St and Clara Barton Blvd.</p> <p>Estimated Construction Cost: \$1,400,000</p>
Out to Bid	DM	<p>Miller-Nash Water, Sewer and Paving Improvements</p> <p>Bid closes May 21, 2020.</p>	<p>Replace existing water line under KCS RR and new wastewater lines under KCS RR to sewer line east of Glenbrook. Also includes 1,100 LF pavement replacement for Miller Road between KCS RR and Glenbrook and storm drainage improvements in Miller. Also includes 1,100 LF of new water line in Nash St. Added 2,100 LF of new wastewater line on Miller December 2017.</p> <p>Length – 650 LF Water and 4,400 LF Wastewater. Estimated cost \$3,500,000</p>

# ENGINEERING DEPARTMENT BID SCHEDULE MAJOR PUBLIC WORKS IMPROVEMENT PROJECTS

**2nd Quarter – April to June 2020 - Updated 04/29/2020**

<b>2020</b>			
<b>Projected Bid</b>		<b>Project</b>	<b>Project Description</b>
Out to Bid	SS	MGR Bikeway (Duck Creek Trail Connection: <i>Glenbrook Trail Connector and Garland-Mesquite Trail Connector</i>  Bid closes on May 14, 2020	Construction of 2,700 LF of a 12' wide concrete trail and a steel truss pedestrian bridge (3-span: 45'-120'-45') between Glenbrook and Duck Creek Drive along Duck Creek. Construction of 2,400 LF of a 12' wide concrete trail and a steel truss pedestrian bridge (1-span: 100') from Greenbelt Pkwy to Duck Creek south of IH-30 for future connection to Mesquite trail. Projected bid is delayed until the agreement with NCTCOG is finalized and approved.  Estimated Construction Cost \$3,000,000
2 <sup>nd</sup> Qtr 2020	GG	Natatorium ADA Ramps at Fire Wheel Pkwy and Crosslands Dr	Provide ADA ramps and Sidewalk  Estimated Cost \$12,057
2 <sup>nd</sup> Qtr 2020	GG	Las Palmas and Biscaye Dr ADA Ramps	Provide ADA ramps  Estimated Cost \$8,500
2 <sup>nd</sup> Qtr 2020	TT	Glenbrook Dr., Centerville Rd to Carroll Dr. and Glenbrook Ct Paving, Water and Wastewater Utility Improvements	Replace existing water line, wastewater line facilities and pavement in S. Glenbrook Dr. from Centerville Rd to Carroll Dr. and on Glenbrook Ct.  Length – 2,500 LF Water, 1,150 LF Wastewater, 100 LF drainage and 2,400 LF Paving Replacements - Estimated Cost \$2,300,000
2 <sup>nd</sup> Qtr 2020	DM	Meadowcreek Park Storm Sewer Improvements	Construction of approximately 4,300 LF of storm sewer pipe to improve drainage in the Meadowcreek Park subdivision.  Length – 4,300 LF – Estimated Cost \$1,200,000 (increasing due to scope change)

# ENGINEERING DEPARTMENT BID SCHEDULE MAJOR PUBLIC WORKS IMPROVEMENT PROJECTS

**2nd Quarter – April to June 2020 - Updated 04/29/2020**

<b>2020</b>			
<b>Projected Bid</b>		<b>Project</b>	<b>Project Description</b>
2 <sup>nd</sup> Qtr 2020	ZK	Avenue H Repaving between Avenue F and Glenbrook Dr. and Sanitary Sewer replacement.	Replacement of approximately 2,200 linear feet of asphalt paving with new concrete and approximately 3,900 linear feet of sanitary sewer pipe of various diameters.  Estimated Cost \$3,000,000
2 <sup>nd</sup> Qtr 2020	GG	Bandera Ln and Northwood Dr ADA Ramps	Provide ADA ramps on the East side of the intersection. Street Department will overlay Northwood Dr. with Asphalt in six to eight months after the ramps are installed.  Estimated Cost \$15,021
2 <sup>nd</sup> Qtr 2020	GG	Innsbrook Dr and Aspen Ln ADA Ramps	Provide ADA ramps on the T intersection  Estimated Cost \$14,595
2 <sup>nd</sup> Qtr 2020	GG	Innsbrook Dr and Vail Dr ADA Ramps	Provide ADA ramps on the T intersection  Estimated Cost \$14,570
2 <sup>nd</sup> Qtr 2020	GG	Innsbrook Dr and Steamboat Springs Dr ADA Ramps	Provide ADA ramps on the East side of the intersection  Estimated Cost \$15,150
2 <sup>nd</sup> Qtr 2020	GG	Innsbrook Dr and Matterhorn Dr ADA Ramps	Provide ADA ramps on Innsbrook Dr and Matterhorn Dr intersection  Estimated Cost \$29,373
2 <sup>nd</sup> Qtr 2020	GG	Cheyenne Trail and Matterhorn Dr ADA Ramps	Provide ADA ramps on Innsbrook Dr and Matterhorn Dr intersection  Estimated Cost \$27,495
3 <sup>rd</sup> Qtr 2020	GG	Wastewater Improvements in Nine unimproved alleys.	Replacement of approximately 11,200 linear feet of 6" wastewater lines with 8" lines.  Estimated Cost \$10,000,000

# ENGINEERING DEPARTMENT BID SCHEDULE MAJOR PUBLIC WORKS IMPROVEMENT PROJECTS

**2nd Quarter – April to June 2020 - Updated 04/29/2020**

<b>2020</b>			
<b>Projected Bid</b>		<b>Project</b>	<b>Project Description</b>
3 <sup>rd</sup> Qtr 2020	GG	Naaman School Rd and Crist Rd Pavement Improvement	Pavement Improvements of about 200 feet to improve the driving condition at Naaman School Rd and Crist Rd intersection  Estimated Construction Cost: \$ 400,000
3 <sup>rd</sup> Qtr 2020	GG	IH30 – Water relocation	TxDOT is widening the IH30 service road at the North side of Bass Pro Dr. Various Franchise Utilities are located in the same alignment as the Water Line  Estimated Cost \$***
4 <sup>th</sup> Qtr 2020	GG	Bridge Remediation Group 1C	Repairs to 13 bridges throughout the City.  Estimated Cost \$4,500,000
4 <sup>th</sup> Qtr 2020	GG	Ballinger Drive, Bonita Drive, Cortez Drive, Lamesa Drive and Belita Drive Water, Wastewater, Paving and Drainage Improvements	Replace existing water and wastewater lines and pavement on Ballinger and Bonita. Wastewater improvements on Kingsley. Replace existing wastewater mains on Alleys between Axe/Flores, Cortez/Lamesa and Lamesa/Belita.  Length – 2,400 LF Water, 6,000 LF Wastewater and 8,300 SY Paving Replacements – Estimated Cost \$2,600,000
4 <sup>th</sup> Qtr 2020	DM	Rosehill Streetscape between IH635 and Bobtown Road.	Construct a trail, median enhancements, hardscape, landscape, irrigation, site furnishings, DART bus stops, pedestrian lighting, street lighting, Rectangular Rapid Flashing Beacon (RRFB) and pavement markings.  Estimated Cost \$2,000,000
4 <sup>th</sup> Qtr 2020	GG	Cardigan St and Grasmere St ADA Ramps	Provide ADA ramps  Estimated Cost \$ 8,548
4 <sup>th</sup> Qtr 2020	TT	Field Knoll Pavement, Water, Wastewater, and Drainage Improvements	Replace existing water, wastewater, and pavement, and install drainage on Field Knoll from Dove Meadow to Guthrie.  Estimated Cost \$1,500,000

# ENGINEERING DEPARTMENT BID SCHEDULE MAJOR PUBLIC WORKS IMPROVEMENT PROJECTS

**2nd Quarter – April to June 2020 - Updated 04/29/2020**

<b>2020</b>			
<b>Projected Bid</b>		<b>Project</b>	<b>Project Description</b>
4 <sup>th</sup> Qtr 2020	GG	Rowlett Creek Wastewater Siphon Replacement at SH 78	Wastewater main aerial crossing replacement to existing Siphons at Rowlett Creek and Spring Creek, just west of SH 78.  Estimated Construction Cost: \$ 2,000,000
4 <sup>th</sup> Qtr 2020	GG	Jupiter Rd and Walnut St Water Line Replacement	Replacement of about 1,200 feet of water line at the back of commercial building located at the Southwest side of Jupiter Rd and Walnut St intersection.  Estimated Construction Cost \$ 500,000
4 <sup>th</sup> Qtr 2020	DCM	Bottleneck Improvements Package 1 – Broadway Blvd/IH30, Forest Ln/Jupiter Rd and Buckingham Rd/Plano Rd	Intersection improvements to increase intersection capacities, reduce congestion and improve operations by adding left- and right-turn lanes.  Estimated Construction Cost \$2,837,000

# ENGINEERING DEPARTMENT BID SCHEDULE MAJOR PUBLIC WORKS IMPROVEMENT PROJECTS

**2nd Quarter – April to June 2020 - Updated 04/29/2020**

<b>2021</b>			
<b>Projected Bid</b>		<b>Project</b>	<b>Project Description</b>
1st Qtr 2021	GG	Bridge Removal and Bridge Remediation at Bradfield Park	Repair the bridge at Bradfield Park and remove the existing pedestrian wood bridge just North of Bradfield Park and Castle Dr.  Estimated Cost \$ 800,000
1st Qtr 2021	DM	Cooper and Southern Gardens Drainage, water and Wastewater Improvements, Ave E at First to Ave B at Mills Branch Tributary 2.	Complete the drainage improvements for the Fifth Street outfall between the Mills Branch tributary 2, west along Ave B to Hopkins, to the Ave D alley and crossing 1 <sup>st</sup> to Ave E.  Estimated Cost \$5,000,000
1st Qtr 2021	TT	Shady Lane Channel Improvements.	Repair existing concrete “U” channel between Shady Lane and Redbud Lane.  Estimated Cost \$600,000
1st Qtr 2021	TT	Ashville Drainage Improvements	Drainage improvements to address flooding issues.  Estimated Cost \$150,000
1st Qtr 2021	TT	Tobin Trail Drainage Improvements	Drainage Improvements between Tobin Trail and Nancy Jane Circle west of South Country Club.  Estimated Cost \$90,000
2nd Qtr 2021	DCM	Holford Road Segment A	Reconstruction of roadway from PGBT north to City Limits including Hike/Bike trail improvements.  Estimated Cost \$8,210,600
4 <sup>th</sup> Qtr 2021	TT	Callejo Improvements, Arapaho to Campbell Road	Paving, Drainage, water and wastewater improvements.  Estimated cost \$8,340,000
4 <sup>th</sup> Qtr 2021	DCM	Bottleneck Improvements Package 2 – Garland/SH190, Campbell/SH190 and Garland/Apollo	Intersection improvements to increase intersection capacities, reduce congestion and improve operations by adding left- and right-turn lanes.  Estimated Construction Cost \$655,000

# ENGINEERING DEPARTMENT BID SCHEDULE MAJOR PUBLIC WORKS IMPROVEMENT PROJECTS

2nd Quarter – April to June 2020 - Updated 04/29/2020

2021			
Projected Bid		Project	Project Description
TBD	TT	Miami Channel Improvements	Channel Improvements from Oates Road to Village Ridge Rd between Miami and Broadway.  Estimated Cost \$***
TBD	DM	Sidewalk between Country Club and Toyah Road	Replacement of existing and new sidewalk along with drainage improvements. Conflicts need to be identified.  Estimated Cost \$500,000
TBD	DM	Spring Creek Trail Connector – Incorporated in Naaman School Road Project	Construction of 1,700 LF of 12' wide concrete trail with a pedestrian bridges between Kingsbridge and Brand along Naaman School Road.  Estimated Cost \$650,000
TBD	TT	Classic Drive (Keen Creek) Channel Improvements	Channel Improvements from W. Walnut Road to Barnes Drive.  Estimated Cost \$***
TBD	TT	Colonel-Palm Valley-Tobin	Drainage improvements to address flooding issues.  Estimated Cost \$***